



# PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

## FIREFIGHTER I SKILLS MENU NFPA 1001, 2013 Edition

<b>Station A</b>	<b>SCBA OPERATIONAL CHECK</b>	<b>MANDATORY</b>
<b>Station B</b>	<b>SCBA DONNING</b>	<b>MANDATORY</b>
<b>Station C</b>	<b>PRIMARY SEARCH AND UTILITY CONTROL</b>	<b>MANDATORY</b>
Station D	SCBA Cylinder Remove-Refill-Replace	Random
Station E	Roof Cut / Roof Ventilation	Random
<b>Station F</b>	<b>GROUND LADDERS</b>	<b>MANDATORY</b>
Station G	Knot Tying / Tool & Equipment Hoisting	Random
Station H	Operating a Hose Line From a Ground Ladder	Random
<b>Station I</b>	<b>HOSELINE ADVANCEMENT</b>	<b>MANDATORY</b>
<b>Station J</b>	<b>Sprinkler Operations</b>	<b>Random</b>
<b>Station K</b>	<b>Ladders and Rescue</b>	<b>Random</b>
<b>Station L</b>	<b>Salvage Operations</b>	<b>Random</b>
Station M	Fire Control	Random
Station N	Portable Extinguishers	Random
Station O	Rope Inspection and Storage	Random
<b>Station P</b>	<b>WATER SUPPLY / PUMP CONNECTION</b>	<b>MANDATORY</b>
Station Q	Vehicle Fire Control	Random
Station R	Using Lighting Equipment	Random
Station S	Riding Fire Apparatus / Working at an Emergency Scene	Random
<b>Station T</b>	<b>Replacing a Burst Hose Section</b>	<b>Random</b>
Station U	Forcible Entry	Random
Station V	Ventilation / Entry	Random
Station W	Forcible Entry / Overhaul	Random
Station X	Standpipe Operations	Random
Station Y	Natural Ground Cover Fire Attack	Random
Station Z	Equipment Inspection and Maintenance	Random
Station AA	Interior Structural Live Fire Suppression	Random
Station AB	Fire Dept. Communication Systems	Random
<b>Station AC</b>	<b>SCBA EMERGENCY OPERATIONS</b>	<b>MANDATORY</b>



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station A - SCBA OPERATIONAL CHECK</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Mandatory Station JPR 5.5.1</b>	<b>Test Site</b>	

**Directions:** Make a pre-use operational check of your SCBA; announce out loud what you are checking and what conditions you find as you proceed. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 12 of the 12 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Checks backpack assembly condition for wear or damage				
2.	Checks straps for full extension and tangles				
3.	Checks cylinder pressure for manufacturer's recommended capacity				
4.	Opens cylinder valve and checks high pressure connection and hose assembly for leaks				
5.	Checks main line valve for proper operation				
6.	Checks regulator pressure gauge to see if it matches cylinder gauge (+/- 100 psi)				
7.	Checks regulator control position for accessibility				
8.	Checks emergency by-pass for proper operation				
9.	Checks service life alarm for proper operation				
10.	Checks facepiece assembly for cracks, tears or broken head straps				
11.	Checks head straps for full extension				
12.	Were all tasks completed in a SAFE manner? ("NO" indicates automatic failure)				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station B - SCBA DONNING</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Mandatory Station JPR 5.3.1</b>	<b>Test Site</b>	

**Directions:** While wearing full protective clothing (helmet, hood, boots, gloves, coat and trousers); demonstrate donning of Self Contained Breathing Apparatus (SCBA). Be fully prepared to enter a hazardous environment. Do you have any questions?

**Evaluator:** The precise sequence of steps #3 through #8 may vary, depending on different makes/models of SCBA and training provided

**Performance Outcome:** Pass/ Fail will be determined by 16 of the 16 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Sets backpack in place on back				
2.	Secures all straps on SCBA				
3.	Dons facepiece and straps				
4.	Checks for facepiece seal				
5.	Confirms exhalation valve operation				
6.	Connects to regulator / facepiece				
7.	Opens cylinder valve fully				
8.	Opens mainline valve fully (if applicable)				
9.	Checks donning mode switch (if applicable)				
10.	All closures secure on coat/trousers				
11.	Coat collar up and secured				
12.	Gloves on				
13.	Hood donned properly and in place				
14.	Helmet with chin strap in place				
15.	PASS Device activated				
16.	Were tasks completed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station C – PRIMARY SEARCH &amp; UTILTIY CONTROL</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Mandatory Station JPRs 5.3.1, 5.3.5, 5.3.9, 5.3.18</b>	<b>Test Site</b>	

**Directions:** Using full protective clothing, SCBA and a hand tool, perform a primary search with a partner following a rope, hose, or using wall contact, maintaining communications and team integrity, shut off utilities (electric and gas) as designated by the evaluator and exit the hazardous environment as a team. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 14 of the 14 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Selects proper tool for search				
2.	Checks door for heat level before entering.				
3.	Stays low to the floor.				
4.	Communicates effectively (verbal/visual/touch).				
5.	Maximum coverage, sweeps with tool or body.				
6.	Executes "crawl-under" correctly.				
7.	Executes "crawl-over" correctly.				
8.	Executes "restricted passages" correctly.				
9.	Completes evolution before quarter (1/4) or 'Low' service alarm sounds				
10.	Shuts off electric panel correctly.				
11.	Shuts off gas meter correctly.				
12.	Operates by-pass / purge on command.				
13.	Exits hazardous area as a team so that a safe haven is found before exhausting air supply, others are not endangered, and team integrity is maintained.				
14.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station D - SCBA CYLINDER REMOVAL, REFILL &amp; REPLACEMENT</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR 5.3.1</b>	<b>Test Site</b>	

**Directions:** Please remove your SCBA cylinder, refill it using a cascade system, and replace it on your SCBA harness. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 16 of the 16 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Checks main valve to determine that the cylinder is off.				
2.	Removes high pressure hose from cylinder.				
3.	Removes cylinder from harness.				
4.	Inspects cylinder for damage.				
5.	Checks hydrostatic test date.				
6.	Connects fill while in charging sleeve.				
7.	Begins with lowest cascade cylinder.				
8.	Opens SCBA cylinder and charging valve.				
9.	When equalized, closes cascade valve.				
10.	Continues steps 8 and 9 until full.				
11.	Closes all valves and releases pressure.				
12.	Disconnects charging hose.				
13.	Replaces cylinder in harness assembly.				
14.	Checks high pressure hose O-ring.				
15.	Records refill on sheet correctly				
16.	Were tasks completed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station E - ROOF / BASEMENT CUT &amp; ROOF / BASEMENT VENTILATION</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR 5.3.12</b>	<b>Test Site</b>	

**Directions:** As an individual, appropriately place the provided ladder on the simulator; take the tools needed for ventilation per the scenario assigned; climb/cross the ladder; and cut a 2' X 2' hole in the roof / flooring material. Cut the first two sides with the power saw and the second two sides with an axe. Once the hole is cut, perform all other tasks needed to complete the ventilation task. Do you have any questions?

**Evaluator:** Check the scenario tested    \_\_\_ **Roof**    \_\_\_ **Basement**

**Performance Outcome:** Roof Evolution will be determined by 18 of the 22 items being performed correctly.  
Basement Evolution will be determined by 14 of the 22 items being performed correctly.

**Note to Evaluator:** This skill evaluation does not test pre-inspection of the saw; however it is the responsibility of the candidate to ensure that the saw will work on the simulator. If the candidate fails to check the saw, and it does not work, runs out of gas, etc., while on the simulator, the station will be deemed unsatisfactorily completed.

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Opens hooks on roof ladder. (if applicable)				
2.	Checks to determine hooks are locked in place. (if applicable)				
3.	Places ladder flat on roof / floor.				
4.	Secures ladder over roof peak. (if applicable)				
5.	Selects, prepares, starts <b>and stops</b> saw before mounting simulator.				
6.	Places tools and STOPPED saw on ladder.				
7.	Sounds roof / floor with tool while ascending / crossing.				
8.	Locates rafters / floor joist and checks roof / floor integrity.				
9.	Starts saw and makes top cut and far cut.				
10.	Maintains secure footing <b>and control of saw</b> while cutting.				
11.	Makes cuts in a straight line.				
12.	Saw chain / blade does not bind / seize up.				
13.	Shuts down saw and transitions to axe.				
14.	Demonstrates acceptable hand position on axe handle.				
15.	Controls swing and arc				

Skill Station E Continued on Next Page



# PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

## Skill Station E Continued

<b>16.</b>	Cuts in sequential order / alignment.				
<b>17.</b>	Shows acceptable feet / body position.				
<b>18.</b>	Completes cut, removes debris with tool.				
<b>19.</b>	Probes for ceiling / area below for obstructions.				
<b>20.</b>	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station F – GROUND LADDERS</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Mandatory Station JPR's 5.3.6, 5.3.9</b>	<b>Test Site</b>	

**Directions:** As a team, remove the extension ladder from the apparatus. Carry the ladder to the building, place it, raise it, extend the fly section, and set for rescue operations. Secure the ladder at the top and/or bottom. Using your partner as a conscious, non-injured victim, assist him down the ladder. Change positions and assist the second victim down the ladder. Untie, lower, and return the ladder to the apparatus. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by passing both Part A and B. **Note 9a, 14a and 3b are MANDATORY.** *PART A:* PASS/FAIL will be determined by “14” YES Marks. *PART B:* PASS/FAIL will be determined by “3” YES Marks

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
<b>Part A</b>					
1a.	Team removes ladder from apparatus and prepares for a two-person carry.				
2a.	Team assumes acceptable position during carry.				
3a.	Team places ladder in line with target.				
4a.	Team raises ladder properly.				
5a.	Team extends fly to correct level for rescue.				
6a.	Team checks ladder for proper angle / position.				
7a.	Team secures halyard.				
8a.	One candidate is assigned to climb ladder and enter window.				
9a.	Team secures ladder at top and/or bottom. <i>(Mandatory to PASS Skill)</i>				
10a.	Team tests ladder for security by attempting to move top or bottom of ladder.				
<b>Part B Rescue</b>					
1b.	Candidate climbs ladder and assists victim (candidate in window) onto ladder				
2b.	Candidate on ladder assists victim down ladder.				
3b.	Was the rescue performed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
<b>Ground Ladder Work Continues to Completion</b>					
11a.	Team unties ropes that are securing ladder.				
12a.	Team retracts fly and lowers ladder.				
13a.	Team lifts and carries ladder to apparatus.				
14a.	Were tasks completed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station G - KNOT TYING &amp; TOOL / EQUIPMENT HOISTING</b>	Test Date	Candidate #
Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.1.2, 5.3.11, 5.3.12	Test Site	

**Directions:** Using an appropriate fire service knot, the candidate will tie knots, bends, and hitches to haul hose and ventilation equipment.

1. Using an approved fire service knot, raise and lower a ventilation tool. Remove the knots.
2. Next, tie a clove hitch, a half-hitch and an overhand safety knot on the uncharged hoseline. Raise and lower the hoseline. Remove the knots.
3. Tie a bowline around an exhaust fan.
4. Finally, tie a figure of eight on a bight. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 9 of the 13 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
<b>1.</b>	Ties an appropriate fire service knot or hitch onto or around a ventilation tool.				
<b>2.</b>	Ties a half-hitch on the handle.				
<b>3.</b>	Ties a guideline to hoist line, using an appropriate knot or hitch				
<b>4.</b>	Performs and controls hoisting, lowering, and guiding of evolution.				
<b>5.</b>	Removes knots.				
	____ Clove Hitch with Half Hitch    ____ Becket or Sheet Bend ____ Figure Eight on a Bight				
<b>6.</b>	Ties a clove hitch and a half-hitch onto an uncharged hoseline.				
<b>7.</b>	Ties an overhand safety knot to secure the clove hitch on the uncharged hoseline				
<b>8.</b>	Performs and controls hoisting, lowering, and guiding of evolution.				
<b>9.</b>	Removes knots.				
<b>10.</b>	Ties bowline around an exhaust fan				
<b>11.</b>	Ties figure of eight on a bight. (Unless accomplished on ventilation tool)				
<b>12.</b>	Join two pieces of rope together using a proper knot or hitch to hoist line (Unless accomplished on tool hoist line) ____ Becket or Sheet Bend    ____ Figure 8 Follow Through    ____ Fisherman's Knot				
<b>13.</b>	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Continued on Next Page



# PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

Evaluator Comments: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station H – OPERATING A HOSE LINE FROM A GROUND LADDER</b>	Test Date	Candidate #
Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.10	Test Site	

**Directions:** Advance the hose line up the ladder, lock in using the ladder belt provided or a leg lock, order the line to be charged, and operate the hose line from the ladder. Order the hose line shut down and descend the ladder with the hose line. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 11 of the 12 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Properly dons life safety harness (ladder belt) if candidate chooses this option.				
2.	Climbs ladder carrying uncharged hose line.				
3.	Locks into ladder with life safety harness or uses leg lock.				
4.	Orders hose line to be "charged".				
5.	Opens nozzle with control.				
6.	Maneuvers nozzle simulating fire attack and demonstrates nozzle control.				
7.	Closes nozzle with control.				
8.	Orders line to be "shut down".				
9.	Releases pressure on hose line.				
10.	Disconnects the life safety harness from ladder or unlocks from leg lock.				
11.	Descends ladder with hose line.				
12.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station I – HOSE LINE ADVANCEMENT</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Mandatory Station JPR 5.3.10, 5.2.3</b>	<b>Test Site</b>	

**Directions:** As a team, prepare two (2) hose loads of 1½” or 1¾” appropriate for an effective fire ground attack in the designated compartments on the pumper. On the signal from the evaluator, advance one hose line inside the building up the stairs to the second floor prepared to attack the fire. Then change positions and advance the second hose line up the extension ladder into the second floor going down the interior stairs prepared to attack the fire on the first floor. Be sure to call for the line to be charged when ready to attack each fire. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 12 of the 16 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Team loads two (2) hose lines on apparatus acceptable for fire ground attack.				
2.	Team appropriately deploys first hose load from the hose bed				
3.	Team advances hose line into building to the first floor.				
4.	Team positions hose in stairwell for attack to the second floor.				
5.	Using proper radio procedures team orders hose line charged.				
6.	Team advances hose line to the second floor.				
7.	Team removes kinks as necessary.				
	<b>TEAM MEMBERS CHANGE POSITION</b>				
8.	Team appropriately deploys second hose load from the hose bed				
9.	Team advances hose line to ladder, executing proper flaking.				
10.	Team climbs ladder with hose on shoulder.				
11.	Team enters window and checks for stability.				
12.	Team executes flaking of excess hose.				
13.	Using proper radio procedures team orders hose line charged.				
14.	Team advances hose line down stairwell to attack fire on the first floor.				
15.	Team removes kinks as necessary.				
16.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station J – SPRINKLER OPERATIONS</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs: 5.3.14</b>	<b>Test Site</b>	

**Directions:** As a team, select the correct size hose and advance **the supply line** to connect to the fire department sprinkler connection. Then, individually, select an appropriate sprinkler stop device from those provided. Insert the stop into the opening of the discharging sprinkler head to control the flow of water. Locate the main control valve, shut the valve off, and then open the valve again. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 9 of 12 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Team selects correct size hose and advances to fire department sprinkler connection <b>(two 100' lines or LDH w/ Storz fitting)</b> .				
2.	Removes caps / breaks caps (if necessary).				
3.	Checks for obstructions.				
4.	Checks gaskets.				
5.	Team makes connection.				
6.	Team connects hose to engine outlets.				
7.	Candidate places ladder, demonstrating acceptable body position on the ladder.				
8.	Candidate demonstrates dexterous insertion of wedge / stop.				
9.	Candidate closes sprinkler head effectively.				
10.	Candidate identifies main control valve.				
11.	Candidate closes main control valve, then opens again on command of evaluator.				
12.	Were tasks completed in a SAFE manner? <b>(NO Indicates Automatic Failure)</b>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station K - LADDERS AND RESCUE</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 – 2013 Edition Chapter 5 Random Station JPR 5.3.9, 5.3.11</b>	<b>Test Site</b>	

**Directions:** As a member of a team, with SCBA and carrying a hand tool, climb a secured extension ladder, enter the window opening and perform a search to locate a victim. Given that the conditions within the structure have fire on the floor **below** the designated search floor, ventilation operations **as required and coordinated with the attack crew**. Using the proper patient drag or carry, remove the victim to an area of safety on the fire floor or stairwell. **Search and rescue should be completed so that the rescuer's air supply is not compromised.** Do you have any questions?

**Evaluator:** You shall serve as the Attack Team and Incident Command during the evaluation.

**Performance Outcome:** Pass/ Fail will be determined by 11 of the 15 items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Selects the proper search and rescue hand tools?				
2.	Proper climbing technique is used on the ladder with the hand tool?				
3.	Checks floor for stability prior to making entry from window?				
4.	Performs proper ventilation techniques?				
5.	<b>Was ventilation coordinated with attack team?</b>				
6.	As a team performs proper search technique?				
7.	Keeps search confined to the area specified? (As directed by the evaluator.)				
8.	Locates victim?				
9.	Remove victim to safe position or location?				
10.	Notification is made to IC (Evaluator) of victim find and location?				
11.	Utilizes proper patient drag or carry to move an unconscious patient?				
12.	Provides for protection of victim's airway?				
13.	Maintains team integrity throughout search operations?				
14.	<b>Evolution completed so that rescuer's air supply was not compromised?</b>				
15.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station L – SALVAGE OPERATIONS</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.14, 5.5.1</b>	<b>Test Site</b>	

**Directions:** As a team, inspect each salvage cover provided; indicate verbally what you are doing and what you find. *As a team, prepare a salvage cover for “one-person” deployment and the other for “two-person” deployment.* Then arrange all the furnishing into an area and cover all them with a salvage cover. Once completed, remove the cover. Next, construct a water chute using one cover and properly position it for use. Finally, from the second cover, construct a catchall. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 18 of 26 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Spreads both salvage covers for inspection.				
2.	Checks for dirt, mildew, rot, holes or other damage.				
3.	Explains how repairs will be made.				
4.	Explains cleaning and drying procedures.				
5.	Prepares cover for a One Person Deployment. <i>Evaluator select which method was used</i> Roll ____    Fold ____				
6.	Demonstrates neatness and stability of finished fold.				
7.	Prepares cover for Two Person Deployment. <i>Evaluator select which method was used</i> Roll ____    Fold ____				
8.	Demonstrates neatness and stability of finished fold				
9.	Prepares arranges all furnishing / contents in an area to be covered.				
10.	Deploys the salvage cover.				
11.	Makes final positioning / adjustment of cover.				
12.	Systematically removes the cover.				
	<b>CONSTRUCT A WATER CHUTE</b>				
13.	Positions step ladder to opening.				
14.	Prepares salvage cover on floor.				
15.	Positions salvage cover with weather side <b>down</b> .				
16.	Places pike poles on opposite sides of the cover.				
17.	Rolls poles inward from opposite sides.				
18.	Hooks poles to ladder rungs / extends to opening.				
19.	Completes final adjustment of chute.				
	<b>CONSTRUCT WATER CATCHALL</b>				
20.	Prepares salvage cover on floor.				
21.	Positions salvage cover with weather side exposed.				
22.	Rolls opposite sides inward about 3 feet.				

**Station L - Salvage Operations continued on the next page**



# PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

## Station L - Salvage Operations Continued

<b>23.</b>	Lays ends of side rolls over at right angle				
<b>24.</b>	Rolls ends into tight roll and tucks into sides				
<b>25.</b>	Makes final position/adjustment				
<b>26.</b>	Were tasks completed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station M - FIRE CONTROL</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.1; 5.3.8</b>	<b>Test Site</b>	

**Directions:** Using the equipment provided, extinguish the fire scenario presented. Be prepared to trade nozzle and back-up positions on the command of the evaluator. Do you have any questions?

**Evaluator:** Check the scenario tested:     Exterior Class "A"     Dumpster

**Performance Outcome:** Pass/ Fail will be determined by 7 of 9 the items being performed correctly.

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Team advances attack line in proper manner for scenario tested.				
2.	Team positions themselves to avoid compromising safety during attach.				
3.	Nozzleman properly operates and manipulates nozzle to knock down fire presented.				
4.	Back-up fire fighter properly manipulates hose line to facilitate nozzleman's job.				
5.	Team effectively breaks up materials involved to ensure water penetration and to expose and extinguish any hidden/residual fires.				
6.	Team evaluates and indicates all materials are extinguished.				
7.	Team assess for patterns of potential origin.				
	ON COMMAND OF EVALUATOR, TEAM RETREATS TO A SAFE LOCATION AND; NOZZLEMAN AND BACK-UP PERSON TRADE POSITIONS. A SECOND ATTACK IS THEN MADE, WITH EVALUATION OF #3 AND #4 MADE FOR NEW NOZZLEMAN AND BACK-UP PERSON.				
8.	Was the fire extinguished? ( <i>Mandatory Skill to Pass</i> )				
9.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station N – PORTABLE EXTINGUISHERS</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.16</b>	<b>Test Site</b>	

**Directions:** Select the proper portable extinguisher from the units present; attack and extinguish the fire presented. Do you have any questions?

**Evaluator Note:** Check the Scenario Tested: \_\_\_ Class “A” Fire \_\_\_ Class “B” Fire \_\_\_ Class “C” Fire

**Performance Outcome:** Pass/ Fail will be determined by 7 of 9 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Properly wears PPE.				
2.	Selects proper extinguisher for class of fire presented.				
3.	Activates extinguisher properly (pulls pin, activates cartridge, etc.) in accordance with specific extinguisher design.				
4.	Approaches fire from upwind (where and as applicable).				
5.	Uses proper application technique for extinguisher and fire involved (range, nozzle motion, avoids "plunging", etc.).				
6.	Completely extinguishes or achieves substantial knockdown of fire.				
7.	Properly retreats/backs away from fire after extinguishing.				
8.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station O – ROPE INSPECTION &amp; STORAGE</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 – 2013 Edition, Chapter 5 Random Station JPR 5.5.1, 5.1.1, 5.1.2</b>	<b>Test Site</b>	

**Directions:** Given the rope and a storage bag, inspect the rope and store it ready for use. Describe any problems / defects found to the evaluator. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 7 of 7 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Removes gloves for proper feel.				
2.	Inspects 100% of rope length visually.				
3.	Inspects 100% of rope length tactilely (by feel).				
4.	Uses proper tactile (feel) technique for rope presented (laid, braid, braid-on-braid or kernmantle).				
5.	Properly “stuff” rope in bag (evaluator may assist – on request - by holding bag for candidate).				
6.	Secures figure-8 stopper on each end of rope.				
7.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station P - WATER SUPPLY and PUMP CONNECTIONS</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Mandatory Station JPR 5.3.15</b>	<b>Test Site</b>	

**Directions:** Using the equipment provided, establish a water supply to the pumper from the hydrant designated by the evaluator. When this task is completed, set the pumper up to draft from a static water source. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by **10 of 14** the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
	<b>HYDRANT SUPPLY</b>				
<b>1.</b>	Removes caps and places wrench.				
<b>2.</b>	Connects hose and hydrant gate to the hydrant in the proper positions.				
<b>3.</b>	Determines that pump operator (evaluator) is ready for water.				
<b>4.</b>	Positions body in proper position before opening hydrant.				
<b>5.</b>	Fire hydrant is fully opened.				
<b>6.</b>	Closes hydrant fully on command of the pump operator.				
<b>7.</b>	Removes hose / gate, checks for draining operation.				
	<b>DRAFT SUPPLY</b>				
<b>8.</b>	Selects proper suction hose(s) (size, lengths).				
<b>9.</b>	Selects proper strainer equipment.				
<b>10.</b>	Makes necessary hose / appliance connections.				
<b>11.</b>	Identifies pumper suction connection.				
<b>12.</b>	Connects assembled hose / strainer to pumper suction port.				
<b>13.</b>	Places strainer in water, properly secures same.				
<b>14.</b>	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station Q – VEHICLE FIRE CONTROL</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.1, 5-3.7</b>	<b>Test Site</b>	

**Directions:** Using the equipment provided, extinguish a vehicle fire. Maintain protection from flash fires, control any fuel leakage, and check for and eliminate any residual/hidden fires. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 7 of 10 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Properly wears full PPE and SCBA				
2.	Identifies automobile fuel type and controls any fuel leaks.				
3.	Team advances attack line in proper manner.				
4.	Nozzleman protects exposures, if present.				
5.	Nozzleman properly operates and manipulates nozzle to knock down fire presented.				
6.	Operates hoseline as to maintain flash fire protection.				
7.	Back-up fire fighter properly manipulates hose line to facilitate nozzleman's job.				
8.	Overhauls fire scene and exposes hidden fires in all vehicle compartments.				
	ON COMMAND OF EVALUATOR, TEAM RETREATS TO A SAFE LOCATION AND; NOZZLEMAN AND BACK-UP PERSON TRADE POSITIONS. A SECOND ATTACK IS THEN MADE, WITH EVALUATION OF #3 AND #4 MADE FOR NEW NOZZLEMAN AND BACK-UP PERSON.				
9.	Was the fire substantially controlled or extinguished? <i>(Mandatory Skill to Pass)</i>				
10.	Were tasks completed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station R – USING LIGHTING EQUIPMENT</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR 5.3.17</b>	<b>Test Site</b>	

**Directions:** You have before you a power source (portable or vehicle mounted), cords and lighting appliances. Given this equipment, establish a working lighting system for a simulated emergency scene. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 5 of 7 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Selects cord of proper length to reach objective.				
2.	Starts portable generator / establishes that other power source (vehicle mounted or inverter) is working.				
3.	Connects cord selected to power source using adaptor(s) if needed.				
4.	Sets up light; connects cord selected to light, using adaptors and/or junction box if needed.				
5.	Turns light on/off.				
6.	Disassembles cords, adaptors, and appliances and returns them to stored condition (as found); shuts off portable generator (if such is used).				
7.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station S – RIDING FIRE APPARATUS / WORKING AT AN EMERGENCY SCENE</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2008 Edition, Chapter 5 Random Station JPR 5.1.2, 5-3.2, 5-3.3</b>	<b>Test Site</b>	

**Directions:** Given PPE and a equipped fire apparatus, properly don your PPE, board the apparatus and prepare yourself for travel. Upon command from the evaluator, dismount the apparatus and be prepared to complete the following assignment (less SCBA). Given all necessary personal protective equipment, and traffic and scene control devices, demonstrate the ability to set up a safe zone around the apparatus; and demonstrate the ability to slow, stop, release, and direct traffic around the safe zone. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 11 of 14 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Completely dons protective clothing prior to boarding.				
2.	Checks seat area for obstruction, loose tools, etc. (Removes same, if present.)				
3.	Uses handrails/secures good footing while mounting.				
4.	Sits in seat provided, engages seatbelt/shoulder harness assembly provided.				
5.	Dons hearing protection (if open or canopy cab).				
6.	Uses eye protection (if open or canopy cab).				
7.	Uses handrails/secures good footing while dismounting.				
	<b>EVALUATOR DIRECTS CANDIDATE TO DISMOUNT</b>				
8.	Wears all required protective clothing for the given traffic scenario.				
9.	Places warning devices appropriately (i.e., 100 – 1,500 feet up stream from traffic).				
10.	Establishes a one lane taper zone (75 – 100 feet) from apparatus using appropriate equipment.				
11.	Identifies the work zone downstream of traffic.				
12.	Establishes flagging station and signals appropriately to: •Slow           •Release •Stop           •Direct traffic				
13.	Always faces approaching traffic when picking up the traffic control devices.				
14.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station T - REPLACING A BURST HOSE SECTION</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.10, 5.5.2</b>	<b>Test Site</b>	

**Directions:** You have before you a burst section of 1 ½” (or larger) hoseline. Using the equipment at this station, replace the burst section of line and indicate that the section is out-of-service (OOS). Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 6 of 7 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Team secures and deploys <b>one (1) or two (2)</b> sections of replacement hose.				
2.	<b>Team stops flow of burst line by; (Evaluator please check method used)</b> ____ hose clamp    ____ kinking hose    ____ close pump panel valve				
3.	Team disconnects burst section and substitutes replacement sections.				
4.	Team removes burst section from vicinity of hose line.				
5.	Team marks/indicates that the defective section is out-of-service (OOS).				
6.	Team appropriately rolls section of hose indicating OOS.				
7.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station U - FORCIBLE ENTRY</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR 5.3.4</b>	<b>Test Site</b>	

**Directions:** Operating as a 2-person team, select the most appropriate tool(s) for the assigned task, and force entry or breach through the identified obstacle (i.e., door or wall) as identified by the evaluator. Do you have any questions?

**Evaluator:** Check the scenario tested:      \_\_\_\_\_ Door      \_\_\_\_\_ Wall

**Performance Outcome:** Pass/ Fail will be determined by 5 of 8 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Selects proper tool(s) for the task.				
2.	Correctly determines how door opens. (if applicable)				
3.	Checks door for heat; tries handle before forcing entry. (if applicable)				
4.	Selects entry technique compatible with door construction, locking mechanism, and other features, or defines the breaching technique for the given task.				
5.	Demonstrates dexterity, skill and team work in use of tools/application of technique.				
6.	Opens door with minimal damage to jamb, frame and door. (if applicable)				
7.	Appropriately breaches wall for intended task. (if applicable)				
8.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station V – VENTILATION / FORCIBLE ENTRY</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR's 5.3.4; 5.3.11</b>	<b>Test Site</b>	

**Directions:** Demonstrate your ability to unlock and open the window presented for ventilation purposes without the use of tools; on command of the Evaluator, select a proper tool and break window glass as directed. Then, use materials provided to temporarily seal up opening. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 7 of 10 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Identifies locking mechanism(s) on the window presented; unlocks same.				
2.	Opens window properly using opening mechanism(s) provided.				
3.	Removes (without damage) any curtains, blinds or other obstructions present.				
4.	Selects an appropriate tool for breaking glass.				
5.	Positions body properly in relationship to window.				
6.	Strikes glass in appropriate place for type of glass and tool selected.				
7.	Removes shards of glass remaining in window pane (if present).				
8.	Removes curtains, blinds, or other obstructions present.				
9.	Uses staple gun and plastic sheeting provided to effectively seal-up opening.				
10.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station W – FORCIBLE ENTRY / OVERHAUL</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.4; 5.3.13; 5.3.14</b>	<b>Test Site</b>	

**Directions:** Select an appropriate tool from those provided. Check the wall for hidden fires by opening it, remove the debris using the equipment provided. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 4 of 6 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Appropriate tool is selected.				
2.	Wall is felt for heat with back of hand before opening. <i>(Evaluator - tell candidate that wall is warm)</i>				
3.	Wall is opened using proper technique for material from which it is constructed.				
4.	Debris is placed in containers provided and removed from the skill station area.				
5.	A sufficient opening is made for proper examination.				
6.	Were tasks completed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station X – STANDPIPE OPERATIONS</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR 5.3.10</b>	<b>Test Site</b>	

**Directions:** Arrange the hose and nozzle provided in a workable package; then select the proper appliances needed for this evolution. Working as a team, carry the hose line into the building and connect to the standpipe, advancing the line to the floor above. On command from the evaluator, advance the line into an assigned area, and demonstrate the ability to open/close the nozzle appropriately, change patterns, and gallonage flow. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 8 of 10 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Hose is packaged in suitable conformation and carried into building.				
2.	2-1/2" x 1-1/2" wye is connected to riser.				
3.	Hose is connected to wye and advanced up stairwell.				
4.	Proper placement of hose in stairwell is made.				
5.	Line is charged, kinks are removed and line is advanced into assigned area and prepared to flow water.				
6.	Candidate opens and controls nozzle to flow water.				
7.	Candidate responds to "change pattern" directive.				
8.	Candidate responds to "change gallonage" directive.				
9.	Candidate closes nozzle appropriately.				
10.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station Y – NATURAL GROUND COVER FIRE ATTACK</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR 5.3.19</b>	<b>Test Site</b>	

**Directions:** Acting as a team, attack and extinguish the ground cover fire that you are confronted with at this station, using the tools and equipment available. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 7 of 10 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Candidate selects and uses appropriate PPE.				
2.	Candidate chooses appropriate tools, extinguisher, and/or hand line.				
3.	Determines/identifies escape route(s), safe haven.				
4.	Determines exposure threats.				
5.	Makes attack from proper direction based on wind, terrain, and fire.				
6.	Constructs a fire line, if appropriate.				
7.	Maintains integrity of fire line.				
8.	Extinguishes fire with hand tools and/or water.				
9.	Completes the assignment.				
10.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station Z - EQUIPMENT INSPECTION &amp; MAINTENANCE</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.5.1, 5.5.2</b>	<b>Test Site</b>	

**Directions:** Before you are a section of hose, a nozzle, and a ground ladder. Inspect each piece of equipment for serviceability. As you perform each inspection, describe to the evaluator what you are looking for and what your findings are. Are there any questions?

**Performance Outcome:** Pass/ Fail will be determined by 14 of 20 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
	<b>HOSE</b>				
1.	Checks outer jacket for wear and damage.				
2.	Checks inner liner for dry rot and cracks.				
3.	Checks coupling attachment/expansion rings.				
	<b>COUPLINGS</b>				
4.	Checks male threads for damage.				
5.	Checks female threads for bending/damage.				
6.	Removes and checks swivel gasket.				
7.	Replaces swivel gasket.				
8.	Explains the necessary maintenance for hose/couplings that should occur after use.				
	<b>NOZZLE</b>				
9.	Checks for external damage.				
10.	Checks for internal damage and debris.				
11.	Checks gasket for damage.				
12.	Checks for ease of operation.				
13.	Explains the necessary maintenance that should occur after use.				
	<b>LADDERS</b>				
14.	Examines all braces, slides, stops, locks, rivets and pulleys.				
15.	Examines halyard for damage.				
16.	Checks pawls for ease of operation and tension.				
17.	Checks rungs for tightness, bends and cracks.				
18.	Checks beams for tightness, bends and cracks.				
19.	Explains the necessary maintenance that should occur after use.				
20.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station AA - INTERIOR STRUCTURAL LIVE FIRE ATTACK</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPRs 5.3.10</b>	<b>Test Site</b>	

**Directions:** Attack as interior fire operating as a member of a team, given an attack line, ladders when needed, personal protective equipment, tools, and an assignment, so that team integrity is maintained, the attack line is properly deployed for advancement, ladders are correctly placed when used, access is gained into the fire area, effective water application practices are used, the fire is approached safely, attack techniques facilitate suppression given the level of fire, hidden fires are located and controlled, the correct body posture is maintained, hazards are avoided or managed, and the fire is brought under control. Are there any questions?

**Performance Outcome:** Pass/ Fail will be determined by 8 of 11 the items being performed correctly

**Evaluator:** Check the scenario tested. (1 out of three must be tested). ALL scenarios will involve Class A fuel.

\_\_\_\_\_ 1st Floor room and contents    \_\_\_\_\_ 2nd Floor room and contents    \_\_\_\_\_ Basement

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Team advances the attack line to the fire area directed.				
2.	Nozzle man chooses the correct nozzle pattern and application technique for the type of fire attack chosen (direct or indirect)				
3.	Back-up team member(s) manipulate(s) the line to facilitate the nozzle man's job.				
4.	At the appropriate time the team advances the hoseline to the correct window and performs hydraulic ventilation.				
5.	Did team members look for and control hidden fires if encountered? Evaluator will note the location of the hidden fire: _____				
6.	Was the fire brought under control in a safe and effective manner with techniques used by the team members?				
7.	Were the proper tools and techniques used/applied by team members by team members?				
8.	Did the team identify and avoid or control all hazards encountered?				
9.	Was all PPE properly worn and used? <i>(NO Indicates Automatic Failure)</i>				
10.	Team integrity & accountability maintained? <i>(NO Indicates Automatic Failure)</i>				
11.	Were tasks completed in a SAFE manner? <i>(NO Indicates Automatic Failure)</i>				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station AB – Fire Dept. Communication Systems</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5 Random Station JPR 5.2.2</b>	<b>Test Site</b>	

**Directions:** Given a Fire Dept. Phone and/or intercom equipment and a procedure the candidate will answer the telephone or operate the intercom system so that a message is relayed appropriately. Do you have any questions?

**Performance Outcome:** Pass/ Fail will be determined by 4 of 6 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
1.	Candidate operates fire department telephone correctly OR				
2.	Intercom system (if applicable)				
3.	Candidate listened actively to the caller, message taken				
4.	Candidate interacted with caller appropriately and courteously (greeting, tone of conversation and closing)				
5.	Correctly identify distribution methods and properly distribute information in a timely manner (handwritten or electronic message, specific place to post message)				
6.	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_ Evaluator # \_\_\_\_\_



## PENNSYLVANIA STATE FIRE ACADEMY FIREFIGHTER I SKILL PERFORMANCE CHECKLIST

<b>Station AC - SCBA EMERGENCY OPERATIONS</b>	<b>Test Date</b>	<b>Candidate #</b>
<b>Reference NFPA 1001 - 2013 Edition, Chapter 5</b> <b>Mandatory Station JPR 5.3.1, 5.3.9</b>	<b>Test Site</b>	

**Directions:** While wearing full protective clothing (helmet, hood, boots, gloves, coat and trousers) and a SCBA unit, the candidate shall demonstrate the following: a conservation of air breathing technique; a procedure for air flow interruption; a technique for air supply depletion. Do you have any questions?

**Evaluator:** Select one procedure from the conservation of air and the depletion of air tasks below; indicate to the candidate which option selected and mark the same on this skill sheet. All candidates must do the SCBA failure procedure.

**Performance Outcome:** Pass/ Fail will be determined by 4 of 4 the items being performed correctly

No.	Task Steps	Initial Test		Retest	
		Yes	No	Yes	No
<b>1.</b>	<b>CONSERVATION OF AIR</b>				
<b>1a.</b>	Upon command from the evaluator, demonstrate controlled breathing (e.g., inhale through the nose, exhale through the mouth, and control breathing rate)				
<b>1b.</b>	Upon command from the evaluator, demonstrate skip breathing (e.g., take a breath and hold, take another breath, exhale, and repeat same)				
<b>2.</b>	<b>DEPLETION OF AIR SUPPLY</b>				
<b>2a.</b>	Emergency procedures when out of air with no air re-supply available; Call a Mayday then activate pass device establish filter breathing while staying as low as possible Exit hazardous area rapidly				
<b>2b.</b>	Emergency procedures when out of air with trans-fill or buddy breathing capability available; <b>Call a Mayday then activate pass device</b> , attach transfill hose or buddy breather hose to both SCBA units; exit hazardous area				
<b>3.</b>	<b>SCBA FAILURE</b>				
	<b>Emergency procedures when air is not flowing into the face piece:</b> 1. Call a Mayday then; 2. <b>Activates PASS Device</b> 3. Check that cylinder is fully open 4. Close mainline, if present 5. Open bypass slowly 6. Close bypass after each breath 7. Open bypass for next breath 8. Exit hazardous area rapidly				
<b>4.</b>	Were tasks completed in a SAFE manner? ( <i>NO Indicates Automatic Failure</i> )				
		<b>PASS</b>		<b>PASS</b>	
		<b>FAIL</b>		<b>FAIL</b>	

Evaluator Comments: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_

Re-Test Evaluator Signature: \_\_\_\_\_

Evaluator # \_\_\_\_\_